



Central Portal for
Philippine Government
Procurement Opportunities

Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 4931470
Procuring Entity CAUAYAN CITY WATER DISTRICT
Title Installation of Separate Transformer (Single Phase)
Area of Delivery Isabela

Solicitation Number:	201711A	Status	Closed
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Shopping	Bid Supplements	0
Classification:	Goods	Document Request List	0
Category:	Electrical Supplies	Date Published	07/11/2017
Approved Budget for the Contract:	PHP 520,000.00	Last Updated / Time	07/11/2017 00:00 AM
Delivery Period:	15 Day/s	Closing Date / Time	13/11/2017 17:00 PM
Client Agency:			
Contact Person:	JAYCIBETH TUNAC RAMIREZ SENIOR ENGINEER B 166 Africano cor. Burgos Sts., District 2 Cauayan City Isabela Philippines 3305 63-078-6521622 jaycibeth_1709@yahoo.com		

Description

Materials

Anchor (Cresoted Log) 8" Dia.x4'-0" 4 pcs
 Bolt, Machine, 5/8" x 8" 4 pcs
 Bolt, Machine, 5/8" x 10" 13 pcs
 Bolt, Machine, 5/8" x 12" 2 pcs
 Bolt, Oval Eye, 5/8" x 9" 2 pcs
 Bolt, Oval Eye, 5/8" x 10" 10 pcs
 Bolt, Single Upset, 5/8" x 10" 5 pcs
 Bracket, Secondary 1 pc
 Clamp, Anchor Rod Bonding, Single Eye 4 pcs
 Clamp, Deadend Strain, #2/0 ACSR 6 pcs
 Clamp Ground Rod, Tamper Proof 1 pc
 Clamp, Guy Straight, 3 Bolt, Heavy Duty Steel 8 pcs

Clamp, Hot Line, #2 - #4/0 ACSR Main to #2 - #4/0 4 pcs
Clamp, Lood Deadend, #2/0 ACSR 4 units
Clevis, Secondary Swinging without spool 6 units
Conductor, Bare, ACSR #2, AWG 6/1 52 mtrs
Conductor, Bare, ACSR #1/10, AWG 6/1 950 mtrs
Connector, Compression 13 pcs
Connector, Split Bolt 2 pcs
Cutout and Arrester Combination 2 sets
Guy Attachment 4 pcs
Insulator, Pin Type, Porcelain, ANSI, Class 55 -5 7 pcs
Insulator, Suspension, 5-3/4" x 10" 12 pcs
Wire, Guy, Steel , 3/8", 7 Strand 160 ft
Pole, Concrete, 30' 9 pcs
Washer, Square, Flat, 2-1/4" x 2-1/4" x 3/16", 13/16" dia. 40 pcs
Washer, Square, Flat, 4" x 4" x 1/2", with 7/8" dia. 4 pcs
Pin, Pole Top, 20" Long 7 pcs
Rod Anchor, Thimble Type Eye, 5/8"x7'-0 4 pcs
Rod, Ground Steel, Galvanized, 5/8" x 10' 1 pc
Spool Insulator, 1 3/4"dia.groove 10 pcs
Transformer, 50 kVA,amorphus 1 unit
7620/13.2y:240/380v

Labor

Quantity/Unit Assembly Units

1. Pole Top Assembly Units

5 sets A1
1 set A2
2 sets A4
1 set A5
1 set A5-1

2. Transformer Assembly Units

1 set G105 1- Transformer, 50 kVA

3. Grounding Assembly Units

1 set M2-1A
4 sets M2-9

4. Guy Assembly units

4 sets E1-2

5. Anchor Assembly Units

4 sets F2-1

6. Size & Pole Type Assembly

9 pcs 30 Feet

7. Conductor Type Assembly

998 meters Conductor, Bare, ACSR #1/0 AWG 6/1

Created by JAYCIBETH TUNAC RAMIREZ

Date Created 06/11/2017

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.